



PRODUCT	PRODUCT WIDTH
9-BUNDLE	23.5" (597mm)
11-BUNDLE	28.5" (724mm)
13-BUNDLE	33.5" (851mm)

NOTES:

1. EXCAVATE BED TO PROPER WIDTH, AND PROPER DEPTH AS REQUIRED BY STATE AND LOCAL CODES.
2. SMOOTH IRREGULARITIES IN THE EXCAVATION. A LEVEL, FLAT SURFACE IS REQUIRED.
3. LAY SEPTIC STACK PIPES IN BED AND ASSEMBLE AS REQUIRED. VOID PIPES ARE TO BE PLACED "BUTTED" NEXT TO ONE ANOTHER. THE DISTRIBUTION PIPE IS CONNECTED BETWEEN ADJACENT BUNDLES BY A BELL COUPLER PROVIDED.
4. ONCE THE PIPES ARE LAID IN THE BED AND CONNECTED, LAY A FILTER FABRIC COVERING THE ENTIRE SYSTEM.

NOTES:

5. BACKFILL SEPTIC STACK PIPES WITH SUITABLE NATIVE MATERIAL (COARSE SAND OR FINE GRAVEL MAY ALSO BE USED, NO HEAVY CLAYS, SILTS, OR DEBRIS SHALL BE INCLUDED).
6. WALK IN PLACE TO COMPACT SOIL ALONG SIDES AND INTERIOR SOIL COLUMNS FIRST.
7. COVER SEPTIC STACK TO A MINIMUM OF 6" OF COVER AND A MAXIMUM OF 24". NO HEAVY OR HIGHWAY VEHICULAR TRAFFIC OVER TOP OF BED IS ALLOWED. AVOID LARGE ROCKS OR DEBRIS IN COVER MATERIAL.

© 2016 ADS, INC.

1	FORMATTING UPDATES AND RENAMED	TJR	03/18/16	
REV.	DESCRIPTION	BY	MM/DD/YY	CHK'D

ADVANCED DRAINAGE SYSTEMS, INC. ("ADS") HAS PREPARED THIS DETAIL BASED ON INFORMATION PROVIDED TO ADS. THIS DRAWING IS INTENDED TO DEPICT THE COMPONENTS AS REQUESTED. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEERS RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

**SEPTIC STACK BED
INSTALLATION (PLAN VIEW)**

DRAWING NUMBER: STD-921



4640 TRUEMAN BLVD
HILLIARD, OHIO 43026

ADVANCED DRAINAGE SYSTEMS, INC.

DRAWN BY	ECM
DATE	3/24/2015
CHK'D BY	
SCALE	NTS
SHEET	OF